

CERTIFICATE OF ANALYSIS

CERTIFICATE No. 0015-20
TEST CERTIFICATE FOR: Slag Blend 30
PRODUCED AT: Sunstate Cement Ltd, Port of Brisbane
SAMPLE IDENTIFICATION: Spot Despatch Sample sample O6P-000694 sampled on 13/1/2020
SAMPLE TESTED AT: Sunstate Cement Ltd, Port of Brisbane


| SPECIFIED PROPERTY | TEST METHOD | AS3972 REQUIREMENTS | | RESULT |
|--|----------------------|---------------------|----------|----------|
| Compressive strength | AS2350.11, AS2350.12 | | | |
| 3 day | | | | 27.2 MPa |
| 7 day | | Minimum | 20 MPa | 39.8 MPa |
| 28 day | | Minimum | 35 MPa | 59.1 MPa |
| Setting time | AS2350.4 | | | |
| Initial | | Minimum | 45 mins | 120 mins |
| Final | | Maximum | 600 mins | 195 mins |
| Soundness | AS2350.5 | Maximum | 5 mm | 1 mm |
| Sulphuric anhydride (SO ₃) | In house | Maximum | 3.5 % | 2.8 % |

| REPORTABLE PROPERTY | TEST METHOD | | | RESULT |
|---------------------|-------------|--|--|------------------------|
| Loss on ignition | AS2350.2 | | | 3.1 % |
| Fineness | AS2350.8 | | | 415 m ² /kg |
| Chloride | AS3583.13 | | | 0.0034 % |

| OTHER PROPERTIES | TEST METHOD | | | RESULT |
|--------------------|-------------|--|--|--------|
| Normal Consistency | In House | | | 30.5 % |

SAMPLING PROCEDURE: Cement samples obtained according to the requirements of AS2350.1

REMARKS: The results of the above tests relate only to the sample as described above.
The blended cement is produced with a nominal 30% GBFS content.



G Santaguiliana
Approved Signatory
27-Feb-2020



NATA accredited laboratory
Laboratory Number: 2191
Accredited for compliance with
ISO/IEC 17025 Testing
The results of the tests,
calibrations and/or measurements
included in this document are
traceable to Australian/national
standards. This document shall not
be reproduced except in full.