

CERTIFICATE OF ANALYSIS

**CERTIFICATE No.** 0384-18

**TEST CERTIFICATE FOR:** SL Cement

**PRODUCED AT:** Sunstate Cement Ltd, Port of Brisbane

**SAMPLE IDENTIFICATION:** Spot Despatch Sample sample W6P-001025 sampled on 13/3/2018

**SAMPLE TESTED AT:** Sunstate Cement Ltd, Port of Brisbane


| SPECIFIED PROPERTY                     | TEST METHOD          | AS3972 REQUIREMENTS |          | RESULT   |
|--|----------------------|---------------------|----------|----------|
| Compressive strength                   | AS2350.11, AS2350.12 |                     |          |          |
| 3 day                                  |                      |                     |          | 33.5 MPa |
| 7 day                                  |                      | Minimum             | 35 MPa   | 48.0 MPa |
| 28 day                                 |                      | Minimum             | 45 MPa   | 67.5 MPa |
| Setting time                           | AS2350.4             |                     |          |          |
| Initial                                |                      | Minimum             | 45 mins  | 120 mins |
| Final                                  |                      | Maximum             | 600 mins | 195 mins |
| Soundness                              | AS2350.5             | Maximum             | 5 mm     | 1 mm     |
| Sulphuric anhydride (SO <sub>3</sub> ) | In House             | Maximum             | 3.5 %    | 2.9 %    |

| REPORTABLE PROPERTY | TEST METHOD |         |        | RESULT                 |
|---------------------|-------------|---------|--------|------------------------|
| Loss on ignition    | AS2350.2    |         |        | 1.0 %                  |
| Fineness            | AS2350.8    |         |        | 340 m <sup>2</sup> /kg |
| Drying Shrinkage    | AS2350.13   | Maximum | 750 µs | 720 µs                 |
| Chloride            | AS3583.13   |         |        | 0.0139 %               |

| OTHER PROPERTIES   | TEST METHOD |  |  | RESULT |
|--------------------|-------------|--|--|--------|
| Normal Consistency | In House    |  |  | 26.0 % |

**SAMPLING PROCEDURE:** Cement samples obtained according to the requirements of AS2350.1

**REMARKS:** The results of the above tests relate only to the sample as described above.



**G Santaguiliana**  
**Approved Signatory**  
**25-May-2018**



NATA accredited laboratory  
 Laboratory Number: 2190 / 2191  
 Accredited for compliance with  
 ISO/IEC 17025

The results of the tests,  
 calibrations and/or measurements  
 included in this document are  
 traceable to Australian/national  
 standards. This document shall not  
 be reproduced except in full.